

Tender No: TMC/ACTREC/Engg/KRS/SQ-112 /Electrical works / HWCC Building/2021-2022.

Sub : Providing main power supply for Pneumatic tube system in HWCC Building at ACTREC.						
ITEM NO	ITEM DESC	UNIT	HSN	Rate	Qty	Total Amount
1	SITC of PVC Casing Capping 1.25 inch with screws, rawal plug etc. along with all accessories complete in all respect on any hard surface/wall/trench/ceiling etc.	Rmt			80.00	
2	SITC of PVC conduit/ Truncking of 25mm size with spacers & saddles screws, rawal plug etc. along with all accessories complete in all respect on any hard surface/wall/trench/ceiling etc.	Rmt			200.00	
3	Supply, fixing, Testing & commissioning of 16A , TPN MCB with enclosure & connected with provided leads on incoming & outgoing side with all fixing arrangemet etc.	Each			2.00	
4	Supply, fixing, Testing & commissioning of 32A 4 pole MCB with enclosure & connected with provided leads on incoming & outgoing side with all fixing arrangemet etc.	Each			1.00	
5	Supply and fixing of 5A/ 15 A,5 pin, switch socket combination board polycarbonate	Each			8.00	
6	SITC of 1core X 2.5 sq. mm flexible copper wire FR PVC	Rmt			350.00	
7	SITC of 1core X 4 sq. mm flexible copper wire FR PVC	Rmt			30.00	
8	SITC of 1core X 6 sq. mm flexible copper wire FR PVC	Rmt			120.00	
9	Supply & laying of CAT 6 cable through casing-capping, PVC conduit for internet and telephone connectivity	Rmt			200.00	
Total Amount						
CGST %						
SGST %						
Total Amount with GST						

In words

Note :

- 1 Material shall be procured according to the specifications as mentioned in the schedule. In case, make of the is not mentioned in the item, prior approval shall be
- 2 The agency is requested to visit the site to know actual scope of work.
- 3 Rate shall be basic only and GST will be extra as applicable
- 4 Material required at site should be assessed by the agency and bill will not be settled for excess/supplied items.
- 5 All the works will have defect liability period of six months.
- 6 You shall engage supervisor/engineer if any for site co-ordination at your cost.
- 7 Material brought to the site for work shall be enclosed at security gate & copy of the same shall be given to engineering dept
- 8 Quantity may vary as per site condition

Date:

sign & seal of contractor